Suryavamshi
Solar Projects LLP

SOLAR PRODUCTS & SERVICES

3 kW PROPOSAL

For

A TYPICAL KERALA HOME

Sample copy: customer name and address removed

End-to-End Rooftop Solar Solutions

“Turning Kerala’s Sunshine into Reliable, Affordable Power.”

Grid-Connected Rooftop Solar Systems • Tier-1 Components • Design, Supply, Installation & Commissioning

Door No.414, Chithira, Muttathiparamb P.O, Cherthala, 688527
9061626868 | suryavamshisolarprojects@gmail.com
Instagram: @suryavamshi_solarprojects | Facebook: Suryavamshi SOLAR Projects

About This Brochure

Thank you for your interest in solar energy solutions from **Sooryavamshi Solar Projects LLP**. We specialise in end-to-end rooftop solar project development for residential and commercial customers — covering feasibility assessment, engineering, procurement, installation, and grid integration.

This document provides general, non-site-specific information about the components, system specifications, indicative process, and standard terms we work with for a typical grid-connected rooftop solar installation in Kerala. Exact pricing, panel count, and layout are customised for each site after a free assessment.

Illustrative Reference System — 3 kWp Single Phase

The specification table below illustrates a typical small residential system. It is provided as a reference only; actual capacity is sized to your monthly consumption and available roof area.

Particulars	Typical Value
Illustrative Capacity	3 kWp, Single Phase
Tilt & Orientation	10–12°, South-facing
Type of Solar Power Plant	Grid-Connected Rooftop
Indicative Roof Area Required	~300 sq. ft.
Roof Type Supported	Flat / Sloped (structure varies)
Typical Generation	12–15 units/day (site dependent)

Standard Components & Specifications

Every system we design uses Tier-1, quality-certified components. The table below summarises the components used, their specification, and typical quantity for the illustrative 3 kWp reference system introduced on the previous page.

Component	Specification	Make	Nos.
Solar Panels	550 Wp Mono PERC / Bifacial, DCR	Adani / Waaree / Vikram	6
Solar PV Inverter	Single/Three Phase On-Grid Inverter with online monitoring	Solis / Growatt / Polycab	1
DCDB	PV fuses at input, DC isolator, Type-2 DC SPD, IP65 enclosure	ABB / Eaton / Mersen	1
ACDB	MCB and Type-2 AC SPD, IP54 rated enclosure (PC/ABS/CRCA)	ABB / Eaton / Mersen / Citel	1
DC Cables	UV-rated solar copper cable, cross-linked sheath & insulation	Apar / Seichem	Ls.
AC Cables	PVC/XLPE aluminium or copper, sized to load	Apar / Polycab	Ls.
Earthing	Maintenance-free chemical earthing, copper-bonded earth rod (14 mm dia / 1.2 m)	Excel Earthing	2 Sets
Lightning Protection	Single spike air termination rod with insulated base & chemical earth kit	Excel Earthing	1 Set
Solar Energy Meter	Watt-hour meter for generation monitoring	L&T	1
Roof Mounting Structure	Hot-dip galvanised / epoxy-coated GP tubes, engineered for flat or sloped roofs	Apollo	1 Set
Installation, Testing & Commissioning	Complies with Electrical Inspectorate & KSEB standards	Sooryavamshi Certified Team	1 Lot
Indicative Project Cost — 3 kWp Reference System			**Rs. 2,05,000/-**

Design, supply, installation, testing and commissioning for the 3 kWp reference system above. Final pricing depends on capacity, roof type, and site conditions.

Statutory / KSEBL Charges (Kerala)

For grid-connected systems in Kerala, the following statutory charges are payable to KSEB Limited (indicative, subject to KSEBL revision):

- Application fee — approx. Rs. 1,000/-
- Solar Plant Registration Fee — approx. Rs. 3,540/- per KW (a portion is typically refunded by KSEBL after commissioning)
- Net Meter (if not provided by KSEBL) — approx. Rs. 5,000/-

General Terms & Conditions

- Pricing depends on roof type — flat roof, sloped/tiled roof, or elevated structure.
- Load enhancement or three-phase conversion, if required, is quoted separately.
- Our standard offer includes documentation, KSEB testing, and formalities up to commissioning with net metering, including cabling to the KSEBL metering point.
- Subsidy documentation (where applicable) is handled by us; subsidy amounts are credited directly to the customer's bank account subject to MNRE approval.
- The Bi-Directional Energy Meter for net metering is procured from KSEB and billed on a monthly rental basis, unless otherwise agreed.
- KSEB registration fees are charged separately; a portion is typically refunded by KSEB after commissioning.
- Remote monitoring via Wi-Fi data logger is included; internet connectivity at site is to be provided by the customer.

Standard Payment Structure

- 70% advance with Purchase Order / booking confirmation.
- 20% on delivery and installation of materials at site.
- 10% on successful commissioning of the system.

Bank Account Details for Payment

Removed from this sample copy

Our bank details are printed on your own quotation, not on this sample.

A formal, site-specific quotation is shared separately once your project scope is finalised.

Delivery, Installation & Commissioning Schedule

- Supply of materials: within 7 days from advance payment.
- Installation: within 7–15 days from delivery of materials.
- Commissioning: within 10 days of completing installation and obtaining KSEBL approvals.

Warranty

- System warranty: 5 years from the date of commissioning.
- Solar PV modules: 25-year performance warranty — output not less than 90% at 10 years and 80% at 25 years.
- Inverter warranty: as per manufacturer terms, typically 5–10 years depending on model selected.

Scope of Work

Sooryavamshi's Scope

- Engineering: complete system design — civil, structural, electrical and mechanical — with construction drawings and specifications.
- Procurement & Construction: sourcing of equipment and materials, delivery to site, complete installation, and testing of all electrical components per manufacturer specification. Commissioning to full operability.
- KSEB Liaison: obtaining feasibility certificate from the local KSEB section office, system registration, coordinating testing and compliance verification, and replacement of the existing meter with a bi-directional net meter.
- Warranty Support: free inspection visits during the warranty period and maintenance support as required. Panel washing is not included and is to be arranged by the customer.
- Post-Installation: training for the customer's engineer/electrician/staff on operating principles, safety, and maintenance. Daily remote monitoring of the system via internet.

Customer's Scope

- Storage & Access: provide site access for delivery of equipment and materials, secure storage space, and crew access as needed during implementation.
- Local Consultation: facilitate coordination with the customer's engineer/electrician/staff, share approved electrical schematics/drawings if available, and obtain any statutory clearances required.
- Remote Monitoring: provide a wireless internet connection near the grid-tied inverter to enable remote monitoring.
- Post-Installation: periodic cleaning of solar panels after installation is complete.

Contact Us

Sooryavamshi Solar Projects LLP
Door No.414, Chithira, Muttathiparamb P.O, Cherthala, 688527
Phone: **9061626868** | Email: **suryavamshisolarprojects@gmail.com**
Instagram: **@suryavamshi_solarprojects** | Facebook: **Suryavamshi SOLAR Projects**

This is a general information document. Figures shown (capacity, generation, roof area, pricing structure) are indicative and vary by site. For a free, no-obligation site assessment and customised quotation, contact us using the details above.